

12" Exterior-Vert Rebar

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
BOL	BOLTS8-IN	100 CNT BOXES OF 8" BOLTS	79 Each	79.000 Ea	1200.0 Each/Day	
BRI	M	Modular Brick	14,292 Pieces	2,117.328 SF	450.0 Pieces/Day	
BRI	MS	Modular Brick Soldier	3,943 Pieces	583.999 SF	300.0 Pieces/Day	
CMU	MW06	6" Mediumweight CMU	3,812 Pieces	3,388.880 SF	175.0 Pieces/Day	
CMU	MW06B	6" Mediumweight CMU-Bull	115 Pieces	102.222 SF	165.0 Pieces/Day	
CMU	MW06BB	6" Mediumweight CMU-B.B.	307 Pieces	273.333 SF	155.0 Pieces/Day	
CMU	MW06BH	6"Lt Wt CMU-1/2 Bullnose	183 Pieces	81.111 SF	170.0 Pieces/Day	
DRI	COPPERDRI	Copper Drip Edge	280 LinFt	279.666 LF	2000.0 LinFt/Day	
FLA	IPCO18"	IPCO 18" Flashing	280 LinFt	279.666 LF	3000.0 LinFt/Day	
GRO	2500PSI	2500 PSI Grout in Cu.Ft.	174 CbcFt	174.240 CF	175.0 CbcFt/Day	
INR	BLUE2"	Blue 2" Rigid Insulation	3,883 SqFt	3,882.880 SF	1500.0 SqFt/Day	
LIC	COPING CF	Limestone Coping in Cu Ft	195 CbcFt	195.000 CF	12.5 CbcFt/Day	
LIL	2X5SILL	2-1/4 x 5 Sills L.F.	45 LinFt	45.000 LF	280.0 LinFt/Day	
LIS	8" BAND	Limestone Band	135 Pieces	360.891 SF	8.0 Pieces/Day	
LIS	ASHLER SF	Limestone in Sq Ft	136 Pieces	723.554 SF	8.0 Pieces/Day	
LIS	QUOIN1	Limestone Quoin 1st	88 Pieces	78.222 SF	8.0 Pieces/Day	
LIS	QUOIN2	Limestone Quoin 2nd	80 Pieces	53.333 SF	8.0 Pieces/Day	
MOR	[A] Type N Port/Lime	1:1:6 Mix	796 CbcFt	795.532 CF	0.0 CbcFt/Day	
REB	#4	#4 Rebar / Give Vert. Ht	993 LinFt	992.667 LF	1800.0 LinFt/Day	
REB	#4BB REBA	#4 Bond Beam Rebar - 240"	852 LinFt	851.999 LF	1800.0 LinFt/Day	
WEE	WEEPPLAS	Plastic Weep Holes	139 Each	139.000 Ea	3000.0 Each/Day	
WIR	HDT9GA12"	Hot-Dipp./Truss 9ga--12"	3,187 LinFt	3,187.055 LF	0.0 LinFt/Day	

Area	Description	Shape	Outside	Inside	Height	Length	Qty	Opn	Odd	Adj	Sheet	Crew
	12" Exterior-Vert Rebar	Rect	M	MW06	14' 0"	316' 0"	1	Opn	Odd			1

Area of Wall	4,424.00 Sqft	Area of Panels
Area of Openings (not panels)	- 494.45 Sqft	0.00 Sqft
Area of Wall minus Openings	3,929.55 Sqft	

Wall Notes: Modular Brick, 6" CMU, 2" Blue Insulation, 18" IPCO flashing, Copper Drip Edge, Plastic Weepholes, 14" Hot Dip Truss 9ga, Bolts 4'-0" on center, #4 Vertical Rebar with 2500 psi Grout @ 48" on center, (enter a quantity for Optional Control Joint that has rubber tee material and 6" Half and Whole Sash CMU),

4" Interior CMU

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
CMU	MW04	4" Mediumweight CMU	3,953 Pieces	3,513.450 SF	185.0 Pieces/Day	
CMU	MW042RIP	4" Med 2" Rip CMU	268 Pieces	59.634 SF	175.0 Pieces/Day	
CMU	MW04B	4" Mediumweight CMU-Bull	180 Pieces	160.000 SF	175.0 Pieces/Day	
CMU	MW04BB	4" Mediumweight CMU-B.B.	67 Pieces	59.778 SF	165.0 Pieces/Day	
CMU	MW04BH	4" Med CMU-Bull Half	172 Pieces	76.444 SF	175.0 Pieces/Day	
GRO	2500PSI	2500 PSI Grout in Cu.Ft.	6 CbcFt	6.072 CF	175.0 CbcFt/Day	
MOR	[A] Type N Port/Lime	1:1:6 Mix	176 CbcFt	175.872 CF	0.0 CbcFt/Day	
REB	#4BB REBA	#4 Bond Beam Rebar - 240"	179 LinFt	179.333 LF	1800.0 LinFt/Day	
WIR	MGT9GA04"	Mill-Gal./Truss 9ga-- 4"	3,278 LinFt	3,277.844 LF	0.0 LinFt/Day	

Area	Description	Shape	Outside	Inside	Height	Length	Qty	Opn	Odd	Adj	Sheet	Crew
	4" Interior CMU	Rect		MW04	12' 2"	360' 6"	1	Opn	Odd			1

Area of Wall 4,385.75 Sqft Area of Panels
 Area of Openings (not panels) - 484.00 Sqft 0.00 Sqft
 Area of Wall minus Openings 3,901.75 Sqft

Wall Notes: 6 CMU, mil gal truss 9ga Wire,

6" Interior CMU

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
CMU	MW06	6" Mediumweight CMU	1,512 Pieces	1,343.778 SF	175.0 Pieces/Day	
CMU	MW062RIP	6" Med 2" Rip CMU	101 Pieces	22.333 SF	175.0 Pieces/Day	
CMU	MW06B	6" Mediumweight CMU-Bull	61 Pieces	54.222 SF	165.0 Pieces/Day	
CMU	MW06BB	6" Mediumweight CMU-B.B.	21 Pieces	18.667 SF	155.0 Pieces/Day	
CMU	MW06BH	6"Lt Wt CMU-1/2 Bullnose	60 Pieces	26.667 SF	170.0 Pieces/Day	
GRO	2500PSI	2500 PSI Grout in Cu.Ft.	4 CbcFt	4.231 CF	175.0 CbcFt/Day	
MOR	[A] Type N Port/Lime	1:1:6 Mix	77 CbcFt	76.685 CF	0.0 CbcFt/Day	
REB	#4BB REBA	#4 Bond Beam Rebar - 240"	56 LinFt	56.000 LF	1800.0 LinFt/Day	
WIR	MGT9GA06"	Mill-Gal./Truss 9ga-- 6"	1,224 LinFt	1,224.372 LF	0.0 LinFt/Day	

Area	Description	Shape	Outside	Inside	Height	Length	Qty	Opn	Odd	Adj	Sheet	Crew
	6" Interior CMU	Rect		MW06	12' 2"	134' 0"	1	Opn	Odd			1

Area of Wall	1,630.33 Sqft	Area of Panels
Area of Openings (not panels) -	164.67 Sqft	0.00 Sqft
Area of Wall minus Openings	1,465.67 Sqft	

Wall Notes: 6 CMU, mil gal truss 9ga Wire,

Piers

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
BOL	BOLTS8-IN	100 CNT BOXES OF 8" BOLTS	4 Each	4.000 Ea	1200.0 Each/Day	
BRI	M	Modular Brick	720 Pieces	106.667 SF	450.0 Pieces/Day	
BRI	MS	Modular Brick Soldier	198 Pieces	29.333 SF	300.0 Pieces/Day	
CMU	MW06	6" Mediumweight CMU	60 Pieces	53.333 SF	175.0 Pieces/Day	
CMU	MW06BB	6" Mediumweight CMU-B.B.	3 Pieces	2.667 SF	155.0 Pieces/Day	
DRI	COPPERDRI	Copper Drip Edge	16 LinFt	16.000 LF	2000.0 LinFt/Day	
FLA	IPCO18"	IPCO 18" Flashing	16 LinFt	16.000 LF	3000.0 LinFt/Day	
GRO	2500PSI	2500 PSI Grout in Cu.Ft.	4 CbcFt	4.066 CF	175.0 CbcFt/Day	
INR	BLUE2"	Blue 2" Rigid Insulation	131 SqFt	130.667 SF	1500.0 SqFt/Day	
LIC	PIER CAP	Limestone Cap	2 Pieces	5.444 CF	5.5 Pieces/Day	
LIS	8" BAND	Limestone Band	7 Pieces	19.556 SF	8.0 Pieces/Day	
LIS	ASHLER SF	Limestone in Sq Ft	7 Pieces	39.111 SF	8.0 Pieces/Day	
MOR	[A] Type N Port/Lime	1:1:6 Mix	29 CbcFt	28.695 CF	0.0 CbcFt/Day	
REB	#4	#4 Rebar / Give Vert. Ht	28 LinFt	28.000 LF	1800.0 LinFt/Day	
REB	#4BB REBA	#4 Bond Beam Rebar - 240"	8 LinFt	8.000 LF	1800.0 LinFt/Day	
WEE	WEEPPLAS	Plastic Weep Holes	8 Each	8.000 Ea	3000.0 Each/Day	
WIR	HDT9GA12"	Hot-Dipp./Truss 9ga--12"	160 LinFt	160.000 LF	0.0 LinFt/Day	

Area	Description	Shape	Outside	Inside	Height	Length	Qty	Opn	Odd	Adj	Sheet	Crew
Piers		Pier	M	MW06	14' 0"	8' 0"	2		Odd			1

Area of Wall	224.00 Sqft	Area of Panels
Area of Openings (not panels) -	0.00 Sqft	0.00 Sqft
Area of Wall minus Openings	224.00 Sqft	

Wall Between Piers

Class	Material ID	Description	Quantity	Amount	Lay Rate	Hand-written notes
BRI	M	Modular Brick	555 Pieces	82.151 SF	450.0 Pieces/Day	
BRI	MS	Modular Brick Soldier	45 Pieces	6.594 SF	300.0 Pieces/Day	
LIL	COP ENT	Limestone Coping - LF	17 LinFt	16.667 LF	50.0 LinFt/Day	
MOR	[A] Type N Port/Lime	1:1:6 Mix	17 CbcFt	17.056 CF	0.0 CbcFt/Day	
WIR	HDT9GA12"	Hot-Dipp./Truss 9ga--12"	30 LinFt	29.643 LF	0.0 LinFt/Day	

Area	Description	Shape	Outside	Inside	Height	Length	Qty	Opn	Odd	Adj	Sheet	Crew
	Wall Between Piers	Rect	M	M	3' 4"	16' 8"	1	Opn				1

Area of Wall	55.56 Sqft	Area of Panels
Area of Openings (not panels) -	11.18 Sqft	0.00 Sqft
Area of Wall minus Openings	44.37 Sqft	